



NOTES:

1. ALL BACKFILL MATERIAL SHALL BE PLACED IN LIFTS NOT TO EXCEED 12 INCHES BEFORE COMPACTION UNLESS AUTHORIZED BY THE ENGINEER DUE TO THE CHARACTER OF THE MATERIAL AND THE COMPACTING EQUIPMENT.
2. EACH LIFT SHALL BE MECHANICALLY COMPACTED TO THE REQUIRED DENSITY PRIOR TO PLACING SUCCEEDING LIFTS OF BACKFILL MATERIAL.
3. COMPACTION TESTS SHALL BE AS REQUIRED BY THE CITY INSPECTOR, BUT IN NO CASE LESS THAN 2 TESTS EVERY 200 FEET OF TRENCH (ONE AT SUBGRADE AND ONE AT 50% OF TRENCH DEPTH).

DRAWING NUMBER	ST-TRE-6
SCALE	NONE
REVISION DATE	12/20
DEPARTMENT	PW