



PAVEMENT PATCH

**NOTES**

1. ALL TRENCHES IN ROADWAY AREAS SHALL BE BACKFILLED AND PATCHED WITH TEMPORARY ASPHALT AT THE END OF EACH WORK DAY, UNLESS PERMISSION IS GRANTED TO DO OTHERWISE BY THE CITY.
2. ALL TEMPORARY PATCHES ON TRENCHES SHALL BE PERMANENTLY PATCHED AS SOON AS POSSIBLE UPON COMPLETION OF WORK WITHIN THE ROADWAY AREA.
3. REPLACE AND RESTORE ALL SURFACE IMPROVEMENTS (I.E. TRAFFIC BUTTONS, CURBING, STRIPING) AS DIRECTED BY THE CITY.
4. IF THERE ARE MORE THAN 3 PARALLEL OR PERPENDICULAR PATCHES PROPOSED WITHIN 100 LINEAL FEET OF ROADWAY, THE DEVELOPER SHALL BE RESPONSIBLE TO GRIND AND OVERLAY THE ENTIRE AREA TO PUBLIC WORKS STANDARDS.

DRAWING NUMBER	STD3-18D
SCALE	NONE
REVISION DATE	12/16
DEPARTMENT	PW