

1. CONSTRUCT CLEANOUTS WITH WYES OR SANITARY "T'S (SWEEPS). STRAIGHT "T'S ARE NOT PERMITTED.

2. ALLOWABLE GRADES ARE 2% (1/4"/FT) MINIMUM TO 100% (FT/FT) MAXIMUM.

3. SEWER MUST BE STRAIGHT BETWEEN ANGLE POINTS, CHANGES IN LINE OR GRADE SHALL BE MADE WITH APPROVED FITTINGS.

4. NORMALLY ONLY ONE(1) CONNECTION TO THE SEWER MAIN PER BLDG. IS ALLOWED. TWO (2) DIFFERENT LAYOUTS ARE SHOWN FOR CLARITY ONLY!

5. NO ANGLE POINTS GREATER THAN 45° ALLOWED.

6. CLEAN OUTS REQUIRED PER THE UNIFORM PLUMBING CODE.

7. ALL SIDE SEWER PIPE SHALL BE PVC (SDR35 WITH RUBBER GASKETED JOINTS, STRONGBACK FERNCO OR ROMAC 501 COUPLERS).

8. MAXIMUM CLEAN-OUT SPACING IS 100 FEET IN STRAIGHT PIPE SECTIONS.

9. TRENCH SAFETY SHALL BE PROVIDED PER LOCAL, FEDERAL AND STATE REGULATIONS.

10. CONNECTION TO SEWER MAIN PER STD DWG 6-2.

11. INSTALL 6" MINIMUM PIPE SIZE IN ROW.

12. INSTALL 6" CD PER STD PLAN 6-3.

13. PRIVATE SIDE SEWER 4" MINIMUM FOR SINGLE FAMILY, 6" MINIMUM FOR ALL OTHER USES.

14. ADJUST CLEANOUTS TO GRADE ON PRIVATE PROPERTY PER STD. DETAIL 6-3 IF IN PAVED AREAS.

15. AT THE BUILDING, ADJUST CD TO GRADE.

16. VIDED INSPECTION REQUIRED FOR PIPE BURST OR SLIP LINED REPAIRS

