



NOTES

1. PVC SIDE SEWER CONNECTIONS TO NEW MAINS SHALL BE FACTORY TEES.
2. TYPE A SHALL BE USED ONLY WHEN MAIN DEPTH EXCEEDS 15 FEET AND AS APPROVED BY THE CITY.
3. CLEAN-OUTS IN PAVED AREAS REQUIRE A CAST IRON LOCKING RING AND COVER. SEE STANDARD PLAN 6-3 FOR CLEAN-OUTS.
4. SIDE SEWERS SHALL BE TESTED IN ACCORDANCE WITH THE CURRENT WSDOT STANDARD SPECIFICATIONS.