



NOTES

- 1 CLEAN-OUT PIPE AND FITTINGS SHALL BE PVC. WITH GASKET FITTINGS, NO GLUE JOINTS ALLOWED.
- 2 A SANITARY TEE OR SWEEP MAY BE INSTALLED IN LIEU OF A WYE AS SHOWN. STRAIGHT TEES ARE NOT ACCEPTABLE.
- 3 FOR NEW PLATS THE VERTICAL RISER PORTION OF THE CLEAN-OUT WILL BE CONSTRUCTED AT TIME OF CONNECTION TO BUILDING TO MINIMIZE DAMAGE, THE 6" WYE AND 6' PVC PIPE W/GASKETED CAPS WILL BE INSTALLED PRIOR TO BUILDING CONNECTION.
- 4 SEWER STUB WILL BE EXTENDED 10' BEYOND PROPERTY LINE TO PREVENT DAMAGE TO CLEAN-OUT AND MINIMIZE CONFLICTS WITH OTHER UTILITIES WHEN SERVICE TO BUILDING IS ACCOMPLISHED.
- 5 A PRESSURE TREATED 2"x4" OR CONCRETE STUBMARKER SHALL EXTEND DOWN TO A MIN OF 24" BELOW GROUND. A MIN OF 36" SHALL EXTEND ABOVE GROUND.
- 6 THE STUBMARKER SHALL BE PAINTED WITH WHITE TRAFFIC PAINT AND THE WORD "SEWER" AND THE DEPTH IN FEET FROM GROUND TO SEWER STUB INVERT SHALL BE PAINTED ON THE MARKER WITH 3" HIGH BLACK PAINTED LETTERS.

DRAWING NUMBER	STD6-3
SCALE	NONE
REVISION DATE	08/19
DEPARTMENT	PW