



**ITB #3174  
DECANT BAY IMPROVEMENTS  
ADDENDUM #1**

Addendum #1 dated October 21, 2019 is issued to:

A. Answers to project questions:

1. **The phasing requirements indicate that each bay shall be modified individually. Can the collection bay be worked on while still leaving two decant bays operational?**

To maximize availability of the collection bays during the construction, the first bay and the collection bay should be constructed simultaneously and once completed the collection bay should be back in operation while the remaining two decant bays are constructed.

2. **Are there structural concerns that warrant building false walls, or can an alternative solution to save time and money be proposed?**

Part of the reason for the new concrete wall is to embed the steel angles for protection against equipment impacts. Also the existing concrete walls and platforms are poured monolithically and the top walkway slab seems to be quite thick to be demoed nice and clean. However we are open to new proposals and alternative solutions. Contractors can both bid on the project as proposed in the plans and propose alternative methods and fees. The city will consider alternative proposals if approved by the engineer.

3. **Can the project start date be in Jan' 2020?**

Yes, the project start date can be in January.

All other terms and conditions remain unchanged.