

NOTES:

- CONTRACTOR TO PROVIDE ALL MATERIALS, TRAFFIC CONTROL, PERMITS, FLAGGING, SHORING AND MISCELLANEOUS WORK TO TAP THE MAIN AND INSTALL THE SIDE SERVICE.
- 2. PROVIDE CLEANOUT BEHIND RIGHT-OF-WAY/PROPERTY LINE PER DETAIL STD. U-SEW-4 WHEN CONNECTION COMPLETED.
- 3. FOR TAPS ON:
 - DI & CI USE SST ROMAC, SMITH BLAIR, OR FORD TAPPING TEE.
 - 3.2. PVC OR CONCRETE, USE ROMAC CB TEE W/SST CLAMP.
- 4. FOR DUCTILE IRON PIPE IN RIGHT-OF-WAY & EASEMENTS, USE RESTRAINING DEVICE AS SPECIFIED BY THE CITY.
- 5. PROVIDE DISTANCE IN FEET FROM TEE/SADDLE TO DOWNSTREAM MANHOLE TO THE CITY.
- 2"x4" BOARD LENGTH AS REQUIRED IN EVEN FOOT INCREMENTS. PAINT TOP 5' WITH WHITE PAINT. STENCIL IN BLOCK LETTERS THE WORD "SEWER" & TOTAL LENGTH OF THE 2"x4" BOARD. LETTERING TO BE 3" IN HEIGHT.
- 7. FOR FURTHER NOTES REFERENCE LYNNWOOD STANDARD SEWER NOTES.



TYPICAL SIDE SEWER CONNECTION

SCALE	NONE
REVISION DATE	01/22
DEPARTMENT	PW

DRAWING NUMBER U-SEW-3

I-SEW-3-Typical-Side-Sewer-Connection.dw